

for IKGPTU website

I.K. GUJRAL PUNJAB TECHNICAL UNIVERSITY

Estd. Under Punjab Technical University Act, 1996
(Punjab Act No.1 of 1997)

Ref.No. : IKGPTU/

Dated :

Quotation Notice

M/s. _____

Subject:- Providing and Fixing of Urinal in Boys Hostel-III (Ground Floor Blocks A & B) at IKGPTU Main Campus, Jalandhar-Kapurthala Highway, Kapurthala.


Dear Sir,

- 2.0 Sealed quotations are invited for :- **Providing and Fixing of Iron net around water coolers at Boys Hostels at IKGPTU Main Campus, Jalandhar-Kapurthala Highway, Kapurthala.** to be executed at I K Gujral Punjab Technical University on terms, conditions and technical specifications enclosed at Annexure-A. The bidders are requested to quote their rates in the Bill of Quantities enclosed alongwith.
- 2.0 Completed bid documents in a sealed envelope super-scribing the name of the work as stated above should be sent through post at the following address:

THE REGISTRAR,
I. K. GUJRAL PUNJAB TECHNICAL UNIVERSITY
JALANDHAR-KAPURTHALA HIGHWAY, KAPURTHALA
PUNJAB - 144603

Before 12:00 Noon of Dt.04/05/2026, Quotations shall be opened at 12:30 hours on the same day in the presence of the bidders or their authorized representatives intending to attend the opening.

- 3.0 In case, the date of submission/opening of tenders happens to be holiday, the quotations shall be received/opened on the next working day.
- 4.0 IKGPTU reserves the right to cancel the bids or postpone the bids and to accept/reject any or all the bids without assigning any reasons thereof.
- 5.0 The validity of the offer shall be 21 days after the date of opening of the bids.
- 6.0 The transfer of bid documents issued/sent to a particular bidder to another bidder is not admissible. Bidders can submit bids/quotations only on the documents issued to him by IKGPTU or downloaded from IKGPTU website – www.ptu.ac.in



(Dr. R.P.S. Bedi)
Dean (P&EP)



IKGPTU Punjab Technical University

Bill of Quantities

(To be filled by Firm/Contractor)

M/s _____ GST No. _____
Address _____ Contact No. _____

Subject: Providing and Fixing of Urinal in Boys Hostel-III (Ground Floor Blocks A & B) at IKGPTU Main Campus, Jalandhar-Kapurthala Highway, Kapurthala.

Providing and Fixing of Urinal in Boys Hostel-III (Ground Floor Blocks A & B) at IKGPTU Main Campus, Jalandhar-Kapurthala Highway, Kapurthala.						
S.No	CSR No.	Description	Quantity	Unit	Rate (in Rs.) (Including GST)	Amount (in Rs.) (Including GST)
1	30.17(B)	Providing and fixing in position vitreous china ware white urinal with concealed or in-built P-trap (size 310 × 370 × 640 mm), with built-in water seal, outlet to wall and water inlet from back, of approved make, as approved by the Engineer-in-Charge, complete in all respects.	12	each		
2	30.20	Providing and fixing P.V.C Waste Pipe Collapsible 32mm complete in all respect.	12	each		
3	30.21 (A) (iii)	Providing and fixing partitions for different types of urinals, made of toughened glass of 8 mm thickness, of size 450 × 900 mm, complete in all respects.	6	each		
4	30.23	Providing and fixing C.P. brass urinal spreader (ocular-regular type), complete with all necessary fittings for urinals, complete in all respects.	12	each		
5	30.66(d)	Providing and fixing in position C.P. brass concealed stop cock / angle valve of 20 mm size with flange, of approved make, as approved by the Engineer-in-Charge, complete in all respects.	12	each		
6	29.60 (c)	Construction of brick masonry inspection chamber of size 450 mm × 450 mm (inside) and up to 0.60 metre average depth, in cement sand mortar 1:5, including cement concrete 1:4:8 (150 mm thick) in foundation, cement concrete 1:2:4 benching, 12.50 mm thick cement plaster in cement mortar 1:2 with a floating coat of 1 mm thick neat cement, R.C.C. slab in cement concrete 1:2:4, 100 mm thick, with 50 mm thick cement concrete topping, complete with R.C.C. inspection chamber cover and frame of size 455 mm × 455 mm, light duty, double seal, conforming to ISI specifications (weight as per ISI), painted with three coats of black bitumastic paint, complete as per standard design.	4	each		

7	29.72 (a)	Making connection of newly laid sewer line into the wall of existing manhole of fully charged sewer, including cost of plugging the sewer, de-silting, removal of sullage water, breaking and making good the khudda, complete in all respects, for sewer connections up to 300 mm internal diameter.	2	each		
8	29.43 (a)	Providing, laying in trenches to correct line, level, gradient and alignment, and jointing of uPVC pipes conforming to IS:15328-2003, Class SN-8, marked, of approved make such as Supreme, Finolex, Kissan, Jain, Prince or equivalent, including cutting, jointing, testing for water tightness, rectification of leakages and defects, and making good, complete with all specials. (All specials and solvent cement shall be of the same make as the pipes), complete in all respects. 110 mm outside diameter	10	rmt		
9	29.43 (c)	Providing, laying in trenches to correct line, level, gradient and alignment, and jointing of uPVC pipes conforming to IS:15328-2003, Class SN-8, marked, of approved make such as Supreme, Finolex, Kissan, Jain, Prince or equivalent, including cutting, jointing, testing for water tightness, rectification of leakages and defects, and making good, complete with all specials. (All specials and solvent cement shall be of the same make as the pipes), complete in all respects. 160 mm outside diameter	15	rmt		
10	30.85(a)	Cutting chase in brick masonry walls or cement concrete floors for embedding G.I. or C.I. pipe lines, and making good the same to its original condition, complete in all respects. Size of chase: 75 mm × 75 mm.	20	rmt		
11	DSR-19.2.2	Providing and laying cement concrete 1:5:10 (1 cement: 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete as per standard design:- 150 mm diameter S.W. pipe	15	rmt		
12	30.72(b)	Providing and fixing in position PVC flexible tube connection of size 15 mm × 450 mm, with C.P. brass nut, of approved make, as approved by the Engineer-in-Charge, complete in all respects.	12	each		
13	30.64(C)	Providing and fixing in position C.P. brass hexa nipple of 15 mm size, of approved make, as approved by the Engineer-in-Charge, complete in all respects.	20	each		
14	30.64 (B)	Providing and fixing in position C.P. brass extension piece of 75 mm length, of approved make, as approved by the Engineer-in-Charge, including connection with various fixtures, complete in all respects.	24	each		
15	6.6	Providing and fixing in position C.P. brass bottle trap of 32 mm diameter with 40 mm water seal, of approved make, as approved by the Engineer-in-Charge, complete in all respects.	12	each		

16	80.81 (iii)(B)(xii)	Providing and fixing in position SWR uPVC special fittings for soil, waste, vent or anti-syphonage pipes, conforming to IS: 14735, including cutting and wastage, cutting holes in walls, roofs or floors and making good the same to its original condition, but excluding the cost of lead jointing, complete in all respects. Single Y-junction with door.	4	each		
17	80.81 (iii)(B)(v)	Providing and fixing in position SWR uPVC special fittings for soil, waste, vent or anti-syphonage pipes, conforming to IS: 14735, including cutting and wastage, cutting holes in walls, roofs or floors and making good the same to its original condition, but excluding the cost of lead jointing, complete in all respects.Elbow 90 Degree (All side socketed)	4	each		
18	28.11 (A)(a)	Providing, laying, jointing, fixing and testing ISI marked uPVC pipes with G.I. specials, conforming to IS 4985, including the cost of G.I. specials such as tees, bends, sockets, elbows, etc., complete for inside the Building.uPVC Pipe 10 Kgf/cm2 20mm i/d	30	rmt		
19	28.11 (A)(e)	Providing, laying, jointing, fixing and testing ISI marked uPVC pipes with G.I. specials, conforming to IS 4985, including the cost of G.I. specials such as tees, bends, sockets, elbows, etc., complete for inside the Building.uPVC Pipe 10 Kgf/cm2 50 mm i/d	12	rmt		
20	N.S.	Providing and Fixing C.P. Jali	10	each		
Grand Total						
Amount In Words						
Signature and stamp of bidder						

TERMS, CONDITIONS AND TECHNICAL SPECIFICATIONS

1. Rates to be quoted by the bidder should be filled in Bill of Quantities.
2. Rates to be quoted by the bidder shall be deemed to be inclusive of all types of direct and indirect taxes imposed by Central/State Govt. and local bodies such as excise duty, sales tax, GST, works contract tax, service tax, royalties, duties, cess, octroi and other levies as applicable and also include all import duties. The rates shall also be inclusive of all taxes, duties and other charges imposed outside the country on the production, manufacture, sale and transport of Contractor's equipment, plant, materials and supplies to be used on or furnished under the contract and on the services performed under the contract. No additional amount shall be paid or claim be entertained on this account by IKGPTU.
3. Rates to be quoted shall also be inclusive of all royalties, fees and other payments in respect of patents, patents right and license(s) which may be payable to patentee, licensee or other person or corporation and shall obtain all necessary licenses/permissions. In case of any breach (whether willfully or inadvertently) by the Contractor of this provision, the Contractor shall indemnify IKGPTU, its officer and employees against all claims, proceedings, damages, costs, charges, loss and liability which they or any of them may sustain, incur or be put to by reason or in consequence directly or indirectly of such breach and against payment of any royalties damages or other money which the IKGPTU may have to make to any persons or pay in total to the patent rights in respect of the users of any machine, instruments, process, articles matter or thing constructed, manufactured, supplied or delivered by the Contractor under this contract.
4. All the works shall be completed within a period of 30 days from the date of issue of letter of acceptance by IKGPTU.
5. Payment Terms:
 - i. 95% payment shall be made on completion of all the work in all respects. Balance 5% payment shall be made after three months of completion of work and removal of defects (if any) in the works.
 - ii. Payment will be made as actual measurement/Qty. at site.
 - iii. Statutory deductions shall be made from the payments made by IKGPTU to the Contractor as per law of the land. The deductions shall be made as per prescribed rates prevalent from time to time. Amount of tax deduction shall be deposited with the concerned authorities and tax deduction certificate shall be issued by IKGPTU.
6. The bidder is advised to visit and examine the site where the work is to be executed and its surroundings or other areas as deemed fit by the bidder and obtain for itself on its own responsibility all information that may be necessary for preparing the bid and execution of the work. The cost of visiting the site and collecting relevant data shall be at the bidder's own expenses. It is a condition of the tender that the tenderer is deemed to have visited the site and satisfied himself with all the conditions prevailing including any difficulties for executing the work.
7. All the pages of this document shall be submitted by bidder duly signed and stamped by the bidder.
8. All the works shall be executed, measured and paid as per Bill of Quantities.