

For IKG PTU website

I.K. GUJRAL PUNJAB TECHNICAL UNIVERSITY

Estd. Under Punjab Technical University Act, 1996
(Punjab Act No.1 of 1997)

Ref.No. : IKGPTU/ P&EP/0/285

Dated : 15/5/26

Quotation Notice

M/s. _____

Subject:- Special Repair in Room No.24 & 25 at IKGPTU Campus-1, S.A.S Nagar, Mohali

Dear Sir,

- 1.0 Sealed quotations are invited for **Special Repair in Room No.24 & 25 at IKGPTU Campus-1, S.A.S Nagar, Mohali** to be executed at I K Gujral Punjab Technical University on terms, conditions and technical specifications enclosed at Annexure-A. The bidders are requested to quote their rates in the Bill of Quantities enclosed alongwith.
- 2.0 Completed bid documents in a sealed envelope super-scribing the name of the work as stated above should be sent through post at the following address:

THE REGISTRAR,
I. K. GUJRAL PUNJAB TECHNICAL UNIVERSITY
JALANDHAR-KAPURTHALA HIGHWAY, KAPURTHALA
PUNJAB - 144603
- 3.0 Before 12:00 Noon of Dt.26/05/2026, Quotations shall be opened at 12:30 hours on the same day in the presence of the bidders or their authorized representatives intending to attend the opening.
- 3.0 In case, the date of submission/opening of tenders happens to be holiday, the quotations shall be received/opened on the next working day.
- 4.0 IKGPTU reserves the right to cancel the bids or postpone the bids and to accept/reject any or all the bids without assigning any reasons thereof.
- 5.0 The validity of the offer shall be 21 days after the date of opening of the bids.
- 6.0 The transfer of bid documents issued/sent to a particular bidder to another bidder is not admissible. Bidders can submit bids/quotations only on the documents issued to him by IKGPTU or downloaded from IKGPTU website – www.ptu.ac.in



(Dr. R.P.S. Bedi)

Dean (P&EP)



I K Gujral Punjab Technical University

Bill of Quantities

(To be filled by the Firm/Contractor)

M/s. _____ GST No. _____

Address _____ Contact No. _____

Subject: Repair in Room No.24 & 25 at IKGPTU Campus-1, S.A.S Nagar, Mohali

Sr. No.	CSR Item no.	Description of Items	Unit	Qty.	Rate (in Rs.) (including GST)	Amount (in Rs.) (including GST)
1	8.11	Stripping and stacking iron sheets of a roof including ridging, flashing, eaves boards gutters and down pipes.	Sqm	138		
2	13.27i ii(a)	Providing and fixing (PPGL) pre-coated painted galvalume sheet roofing (size, shape and pitch of corrugation as approved by Engineer-in-charge	Sqm	138		
3	13.27 (iv)	Providing and fixing Gutter 250mm wide with PPGL 0.50 thick (TCT) manufactured from zinc / aluminium alloy coated high tensile steel, having minimum yield strength of 550 MPa of approved colour fixed by means of self-drilling screws limped washers as per the manufactures guidelines complete in all respect and to the entire satisfaction of engineer in charge.	rmt	15.2		
4	13.65	Providing and Fixing ceiling consisting of 12.5mm thick Gypsum Board of any size G.I. Cradling hanged from the ceiling by means of G.I. hanger complete as per drawings,specifications and to the entire satisfaction of engineer-in-charge.	sqm	24.9		
5	13.21	Ridges and valleys 45 cm overall, in plain G.I. Sheet 0.80mm fixed with galvanized iron J. and L. hooks 10mm diameter, G.I. Limpet and bitumen washers complete	rmt	15.		

I K Gujral Punjab Technical University

Sr. No.	CSR Item no.	Description of Items	Unit	Qty.	Rate (in Rs.) (Including GST)	Amount (in Rs.) (Including GST)
6	13.79	Providing and fixing mineral fibre false ceiling tiles (NRC 0.55 to 0.6) at all heights of size 595X595x16 mm of approved texture, design and pattern. The work shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge.	Sqm	12.5		
7	13.45	Top Khurra 0.6mX0.6m for rain water pipe in 25mm thick cement concrete 1:2:4 over 50.00 thick cement concrete 1:8:16	Each	02		
8	13.51	Bottom Khurra on ground 1.2m x 0.6m consisting of brick on edge laid in cement mortar 1:3 over 75mm cement concrete 1:8:16 including 12.5mm thick cement plaster 1:3.	Each	02		
9	10.11 b(ii)	Cement concrete 1:4:8 with stone aggregate 40mm gauge mixing by mechanical means using concrete mixer volumetric type	Cum	3.4		
10	11.5	First class burnt brick work laid in cement sand mortar 1.5 in foundation and plinth	Cum	1.8		
11	15.9	12.5mm thick cement plaster 1:4	Sqm	8.4		
12	30.95	Dismantling of floor tiles at any floor of the building, laid in cement mortar including dismantling of cement concrete base and disposal of malba at a suitable place within a distance of 100 Mtrs of the complex complete in all respect.	Sqm	39.03		
13	14.115	Providing and laying vitrified floor tiles in different sizes in light colour shades made using full body Technology (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 fine sand), complete (Full body vitrified tiles have pigment in entire body/thickness of tile which makes chips and scratches less noticeable and make na ideal choice for high traffic zones).	Sqm	30.7		
14	30.85 (a)	Cutting chase in brick walls in cement or in floor for embedding G.I. or C.I pipes line and making good the same to its original condition. (Size 150 mm x 150 mm)	Rmt	27.4		

I K Gujral Punjab Technical University

Sr. No.	CSR Item no.	Description of Items	Unit	Qty.	Rate (in Rs.) (including GST)	Amount (in Rs.) (including GST)
15.	18.19	Cold twisted detormed (Ribbed/ Tor steel) Bars (Fe 550 grade as per IS 1786-2008) , for R.C.C works, where not including in the complete rate of RCC including binding, bending and placing in position complete	Qtl	1.9		
16.	10.22	Reinforced cement concrete M-30 mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in superstructure.	Cum	1.7		
17.	9.3	Centering and shuttering for faces of walls, partitions, retaining walls and the like (vertical or battering) including attached pilasters, buttresses etc when curved. Centering and shuttering for faces of walls, partitions, retaining walls and the like (vertical or battering) including attached pilasters, buttresses etc when curved.	Sqm	11.2		
18.	N.S.	Providing & Fixing PVC Panelling	sft	210		
19.	8.31(a)	Scraping white wash and colour wash	Sqm	290.8		
20.	16.65	Preparation of plastered or concrete surface for painting (including sand papering the surface) using ready mixed cement based wall putty by applying two or more coats to get required finish.	Sqm	290.8		
21.	16.10	Distempering with Acrylic washable oil bound distemper (of approved manufacture) two or more coats over one priming coat to give an even shade.	Sqm	290.8		
22.	13.92	Waterproofing of wet areas (Concrete/ Masonary Surface) with high performance polymer modified cementitious coating (DR. FIXIT FASTFLEX / Equivalent) to provide tough film build-up and highly elastic film formation, which accommodates coating without any joints to prevents water leakage. masonry surface complete in all respects.	Sqm	16.7		

I K Gujral Punjab Technical University

Sr. No.	CSR Item no.	Description of Items	Unit	Qty.	Rate (in Rs.) (including GST)	Amount (in Rs.) (including GST)
23.	NSR	Supply and Erection of 3 Star Rating Ceiling fan Suitable size 48" (1200mm) Full Aluminium Body, 3 Nos. of Blades, white in colour. The mounting type is down rod mount. The product should possess a minimum air delivery of 218 CMM. The rated speed of the product must be minimum of 350 revolutions per minute and 5 Nos, of speed. The approximate The product should have a manufacturer's guarantee/ warranty of minimum 2 years. The product should be complete in all respects with fan motor, bladeset, down rod, conopy set, shackle kit, twisted wire etc., including erection & testing of ceiling fans having connection with PVC insulated PVC sheathed tow single core copper conductor (FR) cable 0.75 SQ MM. Complete in all respects as desired by the Engineer in charge of work at site. The Product should be BEE & BIS Certified	Each	10		
24	NSR	Supply and erection of LED Panel 36 Watt Body White shape square type of item Resses/on Surface 2X2 Warranty 2 year 36W LED Colour Temperature CDL(65k/CDL(57)/NWH(4K) Product Dimensions S-595XH-70MM Body Material Metal Width 595mm Height 70mm Power Factor>0.90: System lumens 3200lm: thd<10%: Wattage 36 W, complete along with erection of the same with connections, testing etc, desired by the Engineer-in-charge at site. The certification and Specifications of the LED Fitting's should be as approved by Olo Advisor (Technical), Govt of Punjab vide Letter no.AT/2021/GL/1410-1422 Dated 06/05/2021. Beside this the lighting manufacturer should have inhouse NABL accreted Lab.	Each	21		
Grand Total						
Amount in Words:						
Signature and Stamp of Bidder						

ANNEXURE-A

TERMS, CONDITIONS AND TECHNICAL SPECIFICATIONS

1. Rates to be quoted by the bidder should be filled in Bill of Quantities.
2. Rates to be quoted by the bidder shall be deemed to be inclusive of all types of direct and indirect taxes imposed by Central/State Govt, and local bodies such as excise duty, sales tax, GST, works contract tax, service tax, royalties, duties, cess, octroi and other levies as applicable and also include all import duties. The rates shall also be inclusive of all taxes, duties and other charges imposed outside the country on the production, manufacture, sale and transport of Contractor's equipment, plant, materials and supplies to be used on or furnished under the contract and on the services performed under the contract. No additional amount shall be paid or claim be entertained on this account by IKGPTU.
3. Rates to be quoted shall also be inclusive of all royalties, fees and other payments in respect of patents, patents right and license(s) which may be payable to patentee, licensee or other person or corporation and shall obtain all necessary licenses/permissions. In case of any breach (whether willfully or inadvertently) by the Contractor of this provision, the Contractor shall indemnify IKGPTU, its officer and employees against all claims, proceedings, damages, costs, charges, loss and liability which they or any of them may sustain, incur or be put to by reason or in consequence directly or indirectly of such breach and against payment of any royalties damages or other money which the IKGPTU may have to make to any persons or pay in total to the patent rights in respect of the users of any machine, instruments, process, articles matte or thing constructed, manufactured, supplied or delivered by the Contractor under this contract.
4. All the works shall be completed within a period of 60 days from the date of issue of Work Order by IKGPTU.
5. Payment Terms:
 - i. 95% payment shall be made on completion of all the work in all respects. Balance 5% payment shall be made after three months of completion of work and removal of defects (if any) in the works.
 - ii. Payment will be made as actual measurement/Qty. at site.
 - iii. Statutory deductions shall be made from the payments made by IKGPTU to the Contactor as per law of the land. The deductions shall be made as per prescribed rates prevalent from time to time. Amount of tax deduction shall be deposited with the concerned authorities and tax deduction certificate shall be issued by IKGPTU.
6. The bidder is advised to visit and examine the site where the work is to be executed and its surroundings or other areas as deemed fit by the bidder and obtain for itself on its own responsibility all information that may be necessary for preparing the bid and execution of the work. The cost of visiting the site and collecting relevant data shall be at the bidder's own expenses. It is a condition of the tender that the tenderer is deemed to have visited the site and satisfied himself with all the conditions prevailing including any difficulties for executing the work.
7. All the pages of this document shall be submitted by bidder duly signed and stamped by the bidder.
8. All the works shall be executed, measured and paid as per Bill of Quantities.